

Under J4.2.1.1.2, the on-site wastewater treatment plant is indicated to be 69,000 gpd, yet personnel indicated that it was 650,000 gpd or larger. Please clarify size of the treatment plant.

Answer: Section J4.2.1.1.2 had a typographical error. As indicated in Table 2B, Fixed Inventory, Wastewater Collection and Treatment System for Camp Bullis the plant is a 0.69 MGD plant. The on-site wastewater treatment plant was designed for a continuous flow of 0.69 MGD and two hour peak of 2.3 MGD.